



10th Avenue N & 1st Street N STREET RESURFACING PROJECT NEWSLETTER



Project Schedule



Construction



Roadway Access



Project Contacts



Project Map

PROJECT SCHEDULE



Construction is planned to start Monday, May 23rd, and the project area is shown on the back of this newsletter.

The project is anticipated to last for approximately 4 to 5 weeks. However, construction activities will not take place every day of the week during this time.

Week of May 23rd

- Contractor to start removing defective or non-draining curb and gutter panels and sidewalk panels on Phase A (10th Ave N from Mainstreet to 1st St N and 1st St N from 8th Ave N to 10th Ave N) & Phase B (1st St N from 10th Ave N to 14th Ave N)
- Contractor to pour new curb and gutter panels and sidewalk panels on Phase A & Phase B

Week of May 30th

- Contractor will perform street patching at new concrete areas on Phase B

Week of June 6th

- Contractor will reclaim (grind up) the existing asphalt pavement on Phase A
- Contractor will grade the reclaimed material and pave the first layer of asphalt on Phase A

Week of June 13th

- Turf restoration and seeding behind concrete replacements
- Contractor will mill off the upper 2 inches of existing asphalt pavement on Phase B

Week of June 13th (continued)

- Paving of the final layer of asphalt pavement will occur on Phase A and Phase B

Week of June 20th

- Roadway pavement markings will be installed

CONSTRUCTION



The project will consist of the City's contractor, Northwest Asphalt, removing and replacing defective or non-draining curb and gutter, reclaiming the existing asphalt pavement on Phase A, milling the existing asphalt pavement on Phase B, paving new asphalt, and restriping the roadway.

This work will require temporary traffic control devices and some lane shifting and temporary closures/detours on streets to allow for the work to be completed safely.

The contractor will try to always maintain a safe working environment, but we do ask that you avoid getting close to construction activity.

ROADWAY ACCESS



During construction, the contractor will maintain access to most of the project area and all residences and businesses. However, there is anticipated to be a temporary closure and detour at 10th Ave N & 1st St N, and there may be times during the construction operations in which you will be required to temporarily wait for an operation to be completed. These delays should be minimal, but we please ask for your patience and understanding during the construction process. The contractor will do their best to keep things as normal as possible during construction.

PROJECT CONTACTS



Josh Hrabe, of Bolton & Menk, Inc., is the Construction Observer for the project and will be the main point of contact for residents during construction. He can be reached at (612)-965-2473 or joshhr@bolton-menk.com

Nick Amatuccio, of Bolton & Menk, Inc., is the Project Engineer overseeing the construction process and will serve as one of the main resident contacts. He can be reached at (612)-965-3926 or nickam@bolton-menk.com

Eric Klingbeil is the City Engineer for the City of Hopkins and will be the main contact at the City for this project. He can be reached at (952) 548-6357 or eklingbeil@hopkinsmn.com

Website: The website will be updated approximately weekly once construction starts with the latest project info throughout construction, and residents can sign-up for weekly email and/or text updates through the website. The site URL is www.Hopkins-2022.com.

Text & Email Updates: Through the project website, www.Hopkins-2022.com, you can sign up for text and email updates that you will receive throughout the duration of the project. This is a very efficient and effective way to know what's going on during the project.

PROJECT MAP



 PHASE A

 PHASE B