

Neighborhood Informational Meeting No. 2 2020 Street & Utility Improvements

February 6, 2020



1

Introductions

Matt Mohs, P.E. Bolton & Menk, Inc. Project Manager Cell: 507-601-9487

Matthew.mohs@Bolton-menk.com

Amy Kreofsky, P.E. Bolton & Menk, Inc. Design Engineer




Agenda

- Project Area
- Council Decisions
- Proposed Improvements Design Considerations
- Schedule & Next Steps
- Project Communication
- Estimated Costs and Assessments
- 2D Project Review and Design Questions
- Questions



3



Council Decisions

- Design Direction Provided by the City Council
 - Street width 40-ft (face of curb to face of curb)
 - Bump-outs will not be included on the east side of the Maple Street intersection
 - Sidewalk will be included along the Park
 - Sidewalk will not be installed along the west side of Lincoln in the 300 block
 - Assessment Rates will follow the 20% option instead of the city policy



5

Proposed Conditions Streets

- 40-ft wide matching the existing width
- Asphalt surfacing, concrete curb and gutter, concrete driveway aprons
- 5-ft concrete sidewalk, ADA pedestrian ramps





Proposed Conditions Storm Sewer



- New 8-inch to 18-inch pipe
- Additional inlets at intersections
- Larger inlet grates
- Shallow depth will remain
- 6-inch perforated subdrain with sump pump service stubs



7

Proposed Conditions Storm Sewer Sump Drain Connection 19.33' 5' SIDEWALK TURF 5' SIDEWALK SEE DETAIL ABOVE) 8" PVC DRAIN BASIN (SEE DETAIL ABOVE) 10 LF 4" SDR-26 PVC 10 LF 4

Proposed Conditions Sanitary Sewer & Services



- 8" Diameter PVC Pipe
- Concrete Manholes
- 4" Services to Property Line
- Watertight System
- Shallow depth will remain
- Insulation provided for pipe and services with less than 7-ft of cover



9

Proposed Conditions Watermain & Services



- 8" Diameter PVC
- 1" Copper Services to Property Line (w/ Curb Stop located in the boulevard)
- New Hydrants
- New Valves



Other Utilities

We've met with the local vendors who supply:

- Communications (internet, phone cable)
- Natural Gas
- Electric

Our design is being coordinated with these systems. In fact, MiEnergy plans to relocate three power poles in the coming weeks to accommodate the project.



11

Turf Establishment



- Top Soil
- Fertilizer & Seed
- Hydromulch
- 70% Growth

 The City is requesting that residents supplement watering of the newly seeded areas.
 We will provide watering instructions.



Tentative Project Schedule Summary

Tentative Project Schedule							
Resolution Ordering Preparation of the Preliminary Engineering Report (PER)	Complete						
Prepare Feasibility Report	Complete						
Resolution Receiving Report and Calling for Hearing on Improvement	Complete						
Published Notice of Hearing on Improvement	Complete						
• '	Complete						
Mailed Notice of Hearing on Improvement	Complete						
Neighborhood Informational Meeting #1	Complete						
Improvement Hearing	Complete						
Resolution Ordering Improvement and Preparation of Plans and Specifications	Complete						
Prepare Plans and Specifications	In Progress						
Neighborhood Informational Meeting #2	2/6/20						
Resolution Approving Plans and Specifications and Ordering Advertisement for Bids	2/10/2020						
Advertise for Bids	2/13/2020						
Open Bids	3/5/2020						
Prepare Assessment Roll & Contractor Evaluations	3/5/2020 - 3/9/2020						
Resolution Declaring Cost to be Assessed and Ordering Preparation of Proposed Assessment	3/9/2020						
Resolution for Hearing on Proposed Assessment	3/9/2020						
Publish Notice of Hearing on Proposed Assessment	3/19/2020						
Mailed Notice of Hearing on Proposed Assessment	3/19/2020						
Neighborhood Informational Meeting #3	4/9/2020						
Assessment Hearing	4/13/2020						
Resolution Adopting Assessment	4/13/2020						
Resolution Awarding Contract	4/13/2020						
Begin Construction	May 2020						
Substantial Completion of Construction	September 2020						
End Construction	June 2021						



13

Construction Communication: Newsletter





Real People. Real Solutions.

2020 Street & Utility Improvement Project

Neighborhood Meeting: Thursday, November 7th at 6pm Houston City Hall 105 West Maple Street Houston, MN 55943

Hearing on Improvement: Tuesday, November 12th at 6pm Houston City Hall 105 West Maple Street Houston, MN 55943

Project schedule: Planning – Summer/Fall 2019 Design – Winter 2019/2020 Construction - Summer 2020

Informational Meeting

A <u>Neighborhood Informational Meeting</u> will be held on <u>Thursday.</u>

<u>November 7, 2019, at 6:00 pm at City Hall</u>. Information on project scope, costs, and assessments will be presented at this meeting.

Hearing on Improvement

A <u>Hearing on Improvement</u> will be held on <u>Tuesday, November 12, 2019 at 6:00 pm at City Hall</u>. Please see the enclosed Notice of Hearing on Improvement for more specific information.



The City of Houston is beginning to plan for the 2020 Street and Utility Improvement Project within the following area (map on page 2):



Construction Communication: Project Website

Coming Soon.....

City of Rushford - 2019 Street & Utility Reconstruction



Project Links

Project Overview

Contacts Maps & Documents

Construction Updates

Project Overview

The City of Rushford is beginning to plan for the 2019 Street and Utility Reconstruction Project within

- E Grove Street (Walnut Street to Money Creek Street)
- Walnut Street (E Grove Street to E Rushford Avenue)
- Lamplighters Lane (Street improvements only)

Improvements will include complete replacement of bituminous pavement, curb and gutter, watermain and services, and sanitary sewer mains and services. Underground storm sewer will also be extended into the project area. The estimated cost of the proposed improvements is \$1.825 Million. A portion of the project costs will be assessed to adjacent properties in accordance with Chapter 429 of the





15

Construction Communication: RPR

- Bolton & Menk will have a **Resident Project Representative** on site every day construction is taking place.
- Question, Comments or Concerns should be directed to the RPR. Contact information will be provided.
- · Limit questions to the contractor, staff isn't always completely in the loop on what is happening, RPR is.





Estimated Costs

Table 2 – Preliminary Cost Estimate								
ltem	Co	Estimated nstruction Cost	Estimated Engineering, Administration, and Financing Cost		Total Estimated Project Cost			
Assessable Costs								
Removals, Street & Surface, Misc.	\$	547,375.19	\$	136,892.41	\$	684,267.60		
Sidewalks	\$	88,479.18	\$	22,127.65	\$	110,606.83		
Sanitary Sewer Services	\$	39,490.30	\$	9,876.08	\$	49,366.39		
Water Services	\$	36,971.28	\$	9,246.10	\$	46,217.39		
Total Assessable Costs	\$	712,315.96	\$	178,142.25	\$	890,458.20		
Non-Assessable Cost								
Storm Sewer	\$	107,267.32	\$	26,826.36	\$	134,093.68		
Sanitary Sewer	\$	117,313.15	\$	29,338.70	\$	146,651.85		
Watermain	\$	139,921.07	\$	34,992.69	\$	174,913.77		
Total Non-Assessable Costs	\$	364,501.54	\$	91,157.75	\$	455,659.30		
Total Estimated Project Costs	\$	1,076,817.50	\$	269,300.00	\$	1,346,117.50		



17

Special Assessments

- Corner Lots
 - Long Side 100% Assessed
 - Short Side 100% City Cost
 - If short side is improved first, assessment will be based on short side length.
 - If long side is improved first, assessment will be based on long side length. If short side has been previously improved, then a credit for the short side will be applied to the long side assessment.



Before You Leave

- Provide name and contact information on sign-in sheet
- Please provide specific concerns about your property that we need to know
- Do you have a basement? Do you have a sump pump? If so, we would like to talk to you as it relates to our design.

THANK YOU FOR COMING

