

Real People. Real Solutions.

# Preliminary Engineering Report 2023 Street & Utility Improvements

September 13, 2022




### Agenda


- Project Area
- Existing Conditions
- Proposed Improvements
- Cost Estimate & Financing
- Schedule & Next Steps
- Questions



### **Project Selection**

• Infrastructure Management Plan – August 2019







#### **Project Location**

2023 Street & Utility Improvements

City of Plainview

Figure 1: Project Location







Xref .\Proiect Border.dwg

# Existing Conditions Streets

- Asphalt surface fair to poor condition
- Concrete curb & gutter poor condition
  - minimal between 10<sup>th</sup>
    Street (CSAH 8) & 8<sup>th</sup> Street
- Fragmented sidewalk
- Steep driveway aprons and boulevards





# Existing Conditions Sanitary Sewer

- 8<sup>th</sup> Street to Wabasha Street (TH 42)
  - Systems are approximately 60 years old
  - 8-inch vitrified clay pipe
  - Mineral deposits, offset joints, pipe sags, broken and damaged pipe
  - Manholes Poor condition
- Infiltration increases flows, increases backup risk, increases pumping costs







# Existing Conditions Watermain

- 10<sup>th</sup> Street (CSAH 8) to 6<sup>th</sup> Street
  - 2006: 12-inch ductile iron pipe
- 6<sup>th</sup> Street to Wabasha Street (TH 42)
  - Approximately 60 years old
  - 4-inch cast iron pipe (CIP)
  - CIP of this age is typically brittle, corroded, susceptible to breaks, and reduced in diameter due to mineral buildup
  - Undersized for fire protection





# Existing Conditions Storm Sewer

- 10<sup>th</sup> Street (CSAH 8) to 8<sup>th</sup> Street
  - New Storm Sewer in 2020
  - Drainage discharges West of 10<sup>th</sup> Street (CSAH 8)
  - Some inlets but limited curb & gutter
- 8<sup>th</sup> Street to Wabasha Street (TH 42)
  - Existing 12 to 15-inch concrete pipe
  - Drainage discharges to north at 6<sup>th</sup>
    Street and between 3<sup>rd</sup> & 4<sup>th</sup> Street
  - Catch basins in poor condition





# Proposed Improvements: Reconstruction

- Street Reconstruction
  - 10<sup>th</sup> Street (CSAH 8) to 8<sup>th</sup> Street
- Street & Partial Utility Reconstruction
  - 8<sup>th</sup> Street to 6<sup>th</sup> Street
- Street & Utility Reconstruction
  - 6<sup>th</sup> Street to TH 42




#### **Proposed Improvements**

**2023 STREET & UTILITY IMPROVEMENTS** 

CITY OF PLAINVIEW, MN

FIGURE 4: PROPOSED UTILITY IMPROVEMENTS







#### **Proposed Improvements**

2023 STREET & UTILITY IMPROVEMENTS

CITY OF PLAINVIEW, MN

FIGURE 5: PROPOSED UTILITY IMPROVEMENTS







### Proposed Improvements: Surface

- 36' bituminous pavement
  - 10' driving lanes & 8' parking lanes
  - Standard residential street width
- Concrete curb & gutter
- Concrete sidewalks & driveway aprons



# Proposed Improvements: Sanitary Sewer

- 8 to 10-inch PVC Pipe
- Concrete Manholes
- 6-inch residential service to property line
- Watertight system



### Proposed Improvements: Watermain

- 8-inch PVC watermain
  - 1-inch residential services to property line with curb stop
- New hydrants and valves



# Proposed Improvements: Storm Sewer

- New concrete or plastic pipe
- Additional catch basins
- 6-inch subdrain in street with sump pump services
- 2020 Storm Sewer (CSAH 8)
  - New curb & gutter
  - Adjust castings



### **Project Takeaways**

- Address Surface Needs beyond point of repair/maintenance
- Address Underground Utilities 60 years, end of service life
- Continuous curb & gutter from CSAH 8 to TH 42.
  - Eliminate drainage and erosion issues at west end
- Continuous sidewalk from CSAH 8 to TH 42.
  - Increased safety and accessibility
  - Senior living, school, athletic fields, pool, etc.



#### **Estimated Cost & Financing**

- Total Project Cost:
  - 2021 LRIP Application \$3.35 million (2023 Dollars)
  - 2021 Capital Financial Plan \$3.6 million (2023 Dollars)
  - Current Estimate \$4.8 million
    - Significant construction inflation (25%)
    - Additional utility work
  - 2022 Capital Financial Plan (Updated) \$4.8 million
- We understand project will be financed :
  - Bond Sale Repaid with Utility Funds
  - Cash from Street Reconstruction Fund



### **Tentative Project Schedule Summary**

Table 10 – Tentative Project Schedule	
Council Authorize Preliminary Engineering Report	5/10/2022
Prepare Feasibility Report	Summer 2022
Neighborhood Information Meeting #1	7/27/2022
Resolution Receiving Report	9/13/2022
Resolution Ordering Improvement and Preparation of Plans and Specifications	9/13/2022
Prepare Plans and Specifications	Oct 2022 – Feb 2023
Neighborhood Information Meeting #2	Fall/Winter 2022/2023
Resolution Approving Plans and Specifications and Ordering Advertisement for Bids	2/14/2023
Advertise for Bids	2/16/2023
Open Bids	3/8/2023
Resolution Awarding Contract	3/14/2023
Neighborhood Informational Meeting #3	April 2023
Begin Construction	May 2023
Substantial Completion of Construction	October 2023
Final Completion of Construction	June 2024




# **Construction Process & Project Communication**





#### **Project Website**



#### https://clients.bolton-menk.com/plainviewstreets/



### **Questions?**





### **Questions?**

