

PROJECT BACKGROUND INFO

Downtown Reconstruction Phase 2 Project Public Open House January 30, 2024

The Goal Of This Meeting Is To:

- 1. Review completed steps and potential upcoming project schedule
- 2. Answer questions as to the project process and assessment process
- 3. Discuss the scope of the project
- 4. Review final plans / drawings
- 5. Discuss what is to be expected during construction
- 6. Discuss business related items (access, parking, interruptions, etc.)
- 7. Answer any questions and address any other concerns

Previous Timeline:

Discussed project area & authorized preliminary project items
Completed topographic survey & soil borings
Conducted virtual & in-person open houses
Authorized & completed Feasibility Study
Conducted Improvement Hearing, ordered Improvements, initiated benefit
evaluation, & initiated property condition inspections
Authorized final design & began preparation of final plans/specifications
Finalized project scope with City Council
Held meetings with private utility companies, began completing property condition inspections, & began discussions with impacted property owners

Future Timeline (approximate):

Tonight:	Public Open House
February 2024:	Final design is completed & project permitting is initiated
Feb. / March 2024:	Project is advertised for bidding
March 2024:	Bids are opened & a construction contract is awarded
Spring 2024:	Contracts, insurance, bonds, submittals, & ordering of pipe / materials
May to Nov. 2024:	Project is substantially constructed
Summer 2024:	Assessment benefit evaluation process completed & project financing obtained
Fall 2024:	Assessment Hearing is held
Summer 2025:	Final construction completed, and the project is closed out

Major Scope of Work Items:

Street Reconstruction:

- Street reconstruction of the following streets:
 - o Main Street from Olive Street to just east of Spruce Street
 - o Elm Street, Pine Street, & Spruce Street from Main Street to First Street

- Removal and replacement of entire roadways and curb and gutter
 - Main Street width at the west end = 62 feet (matches Phase 1 width/section)
 - Remaining proposed widths approximately match existing widths:
 - Main Street width at the east end = 52 feet
 - Elm Street width = 52 feet
 - Pine Street & Spruce Street width = 45 feet
- Concrete sidewalks to be removed and replaced at the same locations as existing
 - Widths to vary as follows:
 - Main Street at the west end = 9 feet
 - Main Street at the east end = 6 feet
 - Elm Street = 7 feet
 - Pine Street = 6 feet
 - Sidewalks in City Square Park to remain
 - o All pedestrian ramps to be upgraded per ADA requirements
- Partial removal and replacement of driveways
- Replacement and modification of the lighting and signing
- Removal of trees replacement of trees in the residential area

Utility Improvements:

- Sanitary sewer
 - o Replacement of sewer main, manholes, and services along Main Street & Elm Street
- Watermain
 - o Replacement of watermain, services, and hydrants along Main Street & Elm Street
 - Upsizing of watermain to 8-inch diameter
 - \circ $\;$ Addition of watermain looping along Spruce Street $\;$
- Storm sewer
 - o Replacement of storm sewer on Main Street & Elm Street
 - Addition of new storm sewer to improve drainage
 - \circ $\;$ Draintile & future stormwater reuse mains along the back of curb

What to Expect During Construction:

- Noise, dust, vibration
- Temporary water shut-offs
- Possible temporary water system
- Limited access/parking and access closures
- Possible business interruptions

Who Can I Contact With Future Questions or To Get An Update On The project?

Feel free to contact the City Engineer Jake Saulsbury, P.E. 612-756-4319 jake.saulsbury@bolton-menk.com or the Project Manager: Ryan Johnson 952-426-8335 ryan.johnson@bolton-menk.com

*Updates during construction will be on the project website at <u>https://clients.bolton-menk.com/waconiadowntown/</u> and on the link at the bottom of the City's website at <u>www.waconia.org</u>.