## Cleveland Avenue West Area Street & Utility Improvements Project

March 2024

## **Sump Pump Information**

The project will install six-inch sump pump collector drains installed one-foot behind back of curb and will run parallel with the street. These drains will give residents an opportunity to connect their sump pump discharge lines to avoid the surface discharge that commonly occurs causing pavement deterioration. A sump pump line will be stubbed out to the back side of the sidewalk for each property. The construction representative will work with you on the proper location of these stubs. If you have an existing sump pump line discharging to the street, it will be connected to the new subdrain by the contractor as part of the project.